

CCR PRE-DIVE CHECKLIST

P - Pressure

Confirm Pressures. Push on every manual gas addition, while checking gauge does not drop. Do this for O₂, Dil, ADV, BCD, Dry Suit and Bailout(s). If in water, breathe from all Bailout UW.

R - Rebreathe

Breathe from the loop, while confirming PO₂ is maintained at appropriate level. Confirm scrubber is operational.

E - Electronics

While breathing from the loop, verify all PO₂ monitors agree, and that all proper parameters have been programmed (SP, Gases, GFs, ...).

D - Direction (Above & Under Water)

I - Immerse (Signal Team Mates)

V - Vent (BCD - Dry Suit - Loop)

E - Equalize (Ears - Loop - Dry Suit/BCD)